

NATIONAL CERTIFIED TESTING LABORATORIES

FIVE LEIGH DRIVE • YORK, PENNSYLVANIA 17406 • TELEPHONE (717) 846-1200 FAX (717) 767-4100

www.nctlinc.com

Florida Building Code TAS 201-94 Florida Building Code TAS 202-94 Florida Building Code TAS 203-94

STRUCTURAL, IMPACT & CYCLING TEST REPORT SUMMARY

RENDERED TO:

Acurlite Structural Skylights

1017 North Vine Street Berwick, PA 18603

PRODUCT TYPE: Fixed Skylight Assembly

SERIES/ MODEL: "Secure Series"

Summary of Results							
Specimen 1	TAS 202	+ 120.0 psf	- 120.0	psf			
Specimens 2, 3, 4	TAS 201/203	+ 120.0 psf	-120.0	psf			
Air Infiltration per	Air Infiltration per ASTM E283 in accordance with TAS 202-94 Infiltration: 0.01 cfm/ft ²						
Water Penetration	Water Penetration Resistance per ASTM E331 in accordance with TAS 202-94						
	18 psf - Passed/No water penetration						
Static Air Pressure	per ASTM E330 ii	n accordance with	1 TAS 202	-94			
Design Load Pressu	re	+ 120.0 psf	- 120.0	psf			
Overload/ Structural	Load Pressure	+ 240.0 psf	- 240.0	psf			
Forced Entry Resistance per ASTM F588 in accordance with TAS 202-94							
Passed – Grade 10							
Specimens 2,3,4							
Small Missile Impa	ct/ Pressure Load	ing in accordanc	e with TA	S 201-94			
Impacts rejected wit distress	hout allowing pene	tration and the pro	duct shows	s no resultant failure or			

Test Completed: 07/25/19 Revision Date: 01/05/22

Reference must be made to Report No. NCTL-110-20884-2 dated 08/27/19 for complete test specimen description and data.

For National Certified Testing Laboratories

Justin Bupp

Laboratory Manager

DIGITAL SIGNATURE

NATIONAL CERTIFIED TESTING LABORATORIES



FIVE LEIGH DRIVE • YORK, PENNSYLVANIA 17406 • TELEPHONE (717) 846-1200 FAX (717) 767-4100 www.nctlinc.com

Florida Building Code TAS 201-94 Florida Building Code TAS 202-94 Florida Building Code TAS 203-94

STRUCTURAL, IMPACT & CYCLING PERFORMANCE TEST REPORT

NCTL-110-20884-2

REPORT TO:

ACURLITE STRUCTURAL SKYLIGHTS 1017 NORTH VINE STREET BERWICK, PA 18603

REPORT NUMBER: NCTL-110-20884-2 REPORT DATE: 08/27/19 REVISION DATE: 01/05/22

PRODUCT TYPE: FIXED SKYLIGHT ASSEMBLY

SERIES/ MODEL: "SECURE SERIES"



NATIONAL CERTIFIED TESTING LABORATORIES

FIVE LEIGH DRIVE • YORK, PENNSYLVANIA 17406 • TELEPHONE (717) 846-1200

FAX (717) 767-4100 www.nctlinc.com

Report Number NCTL-110-20884-2

Report Date 08/27/19 Revision Date 01/05/22

Report To Acurlite Structural Skylights

1017 North Vine Street Berwick, PA 18603

Date Testing Started 03/27/19 **Date Testing Completed** 07/25/19

Specification: Florida Building Code TAS 201-94

Impact Test Procedures

Florida Building Code TAS 202-94

Criteria for Testing Impact and Non-Impact Resistant Building Envelope

Components using Uniform Static Air Pressure

Florida Building Code TAS 203-94

Criteria for Testing Products Subjected to Cyclic Pressure Loading

Description of Specimen Tested

Note: All dimensions are in the order (Width x Height x Thickness) unless otherwise noted.

Model/ Series "Secure Series"

Configuration Fixed Skylight

Frame Size Overall

Specimen 1 (sloped)

4331 mm x 3324 mm (170.5" x 130.875") high by 2235 mm (88") deep

Specimens 2-4

4331 mm x 3324 mm (170.5" x 130.875")

Viewing Area <u>All Specimens</u>

Large Fixed

1324 mm x 2457 mm (52.125" x 96.75")

Small Fixed

1324 mm x 1194 mm (52.125" x 47")

Specimen 1 Gable End

2032 mm x 851 mm (80" x 33.5")

Frame Type Extruded aluminum

Joint Construction Frame

The verticals were fastened to the horizontals with (2) screws. The purlins were fastened to the verticals with (6) screws and a metal mounting lug

that was fastened with (3) 3/8" bolts.

Glazing Components

Overall 33.02 mm (1.300") nominal

Glass Thickness (1) Lite of 6 mm (0.220") nominal tempered glass to the exterior and (1)

lite of laminated glass to the interior

Laminated Glass (2) Lites of 6 mm (0.220") nominal heat strengthened glass separated by

a 1.52 mm (0.060") Solutia "Saflex" PVB interlayer

Spacer Type/Size 14.73 mm (0.580") Aluminum spacer (Type A1-D)

Glazing System

Exterior glazed with a multi-fin gasket back-bedding and a screw applied pressure plate with (2) strips multi-fin gasket. The 1/4 - 20 x 2 1/2 HWH type F and 1/4 - 20 x 3 HWH screws were located 64 mm and 70 mm (2.5"

and 2.75") on center at the rafter and left purlin. The horizontal sections were sealed with structural silicone at the exterior

Weatherstrip No weatherseals employed

Operating Hardware No operating hardware employed

Auxiliary

Type Extruded aluminum flashing Location Exterior perimeter of the sample

Type Extruded aluminum/ plywood panel fillers
Location Back side/ close off of mock up to chamber

Type Extruded aluminum glazing adaptor

Location Horizontal members fastened with (9) screws

Type Extruded aluminum "purlin" pressure plate screw adaptor Location Gable end fastened to the frame with evenly spaced screws

Reinforcement No reinforcement employed

Weep Description

Size 19.05 mm (0.75") Gap in sill pan sponge gasket

Location Sill/ rafter intersection

Interior/ Exterior

Surface Finish Painted aluminum

Sealant

Location Exterior perimeter of the glazing, horizontal member back-bedding

flashing to frame

Material Silicone

Insect Screen No screen employed

Installation Method The assembly was installed in a steel/ plywood test chamber. The

assembly was fastened to the chamber with aluminum angles at each end of the rafters. The angles were fastened to the chamber with (2) $1/2-13 \times 1-1/2$ grade 5 Hex Hd per angle. The rafter was fastened to the angles with 2 $1/2-13 \times 4$ 1/2" long Hex Hd cap screw with lock washers and nuts. The gable end was fastened with aluminum angles at the sill and (2) 1/4

bolts and nuts.

Test Results - TAS 202

<u>Test Method</u> <u>Test</u>

ASTM E283 Air Leakage Resistance

Information at 1.6 psf:

Maximum Allowable = 0.30 cfm/ft² Infiltration Rate/ Area = 0.01 cfm/ft²

Test Method ASTM E547 Test

Water Resistance Test

ASTM E347 Water Resistance Tes

The test specimen complies with the requirements of TAS 202 at 5.0 gph/ft²

No Leakage after 1 cycle of 15 minutes at 18 psf

Test Method ASTM E330 Test

Static Air Pressure Tests

Half Test Load - ± 120 psf

Positive = No damage Negative = No damage

Design Loads - ± 120 psf

<u>Vertical</u>

Measured Deflection Positive = 0.108 inches Measured Deflection Negative = 0.104 inches

Measured Permanent Set $_{Positive} = 0.004$ inches Measured Permanent Set $_{Negative} = 0.002$ inches

Horizontal

Measured Deflection $_{Positive}$ = 0.411 inches Measured Deflection $_{Negative}$ = 0.002 inches

Measured Permanent Set $_{Positive} = 0.018$ inches Measured Permanent Set $_{Negative} = 0.008$ inches

<u>Purlin</u>

Measured Deflection $_{\text{Positive}}$ = 0.451 inches Measured Deflection $_{\text{Negative}}$ = 0.025 inches Measured Permanent Set $_{\text{Positive}}$ = 0.033 inches

Measured Permanent Set _{Negative} = 0.012 inches

Test Loads - ± 240 psf

Vertical

Measured Deflection $_{\text{Positive}}$ = 0.206 inches Measured Deflection $_{\text{Negative}}$ = 0.192 inches

Measured Permanent Set Positive = 0.002 inches Measured Permanent Set Negative = 0.002 inches

Horizontal

Measured Deflection $_{\text{Positive}}$ = 0.007 inches Measured Deflection $_{\text{Negative}}$ = 0.029 inches

Measured Permanent Set Positive = 0.008 inches Measured Permanent Set Negative = 0.020 inches

Purlin

Measured Deflection $_{\text{Positive}}$ = 0.164 inches Measured Deflection $_{\text{Negative}}$ = 0.267 inches Measured Permanent Set $_{\text{Positive}}$ = 0.027 inches Measured Permanent Set $_{\text{Negative}}$ = 0.028 inches

NOTE: Deflection and Permanent Set measurements taken on the vertical, horizontal and

purlin with a 0.4%/ 10.46 mm (0.412") for the vertical, 5.28 mm (0.208") for the

horizontal and purlin permanent set limit.

NOTE: Upon completion of testing there was no structural distress indicative of failure

Test Results - TAS 201

Test

Small Missile Impact

Type and weight of missile: (10) 2 g steel ball Speed 130.0 ft/ sec.

*All impacts were performed on the left lite of glass

	Location
Specimen 2	
Impact	Upper Left Corner of Glazing
Impact	Midspan of Right Side of Glazing
Impact	Lower Left Corner of Glazing
Specimen 3	
Impact	Upper Right Corner of Glazing
Impact	Midspan of Left Side of Glazing
Impact	Lower Right Corner of Glazing
Specimen 4	
Impact	Top Midspan of Glazing
Impact	Center Midspan of Glazing
Impact	Bottom Midspan of Glazing

NOTE: All missile impacts were rejected without penetration, tearing, or separation of the laminate. Shattered sacrificial and laminated glass. No visible damage to the frame was observed.

Test Results - TAS 203

Test

Cyclic Wind Pressure Loading

After completion of the impact tests, the test specimens were pressure cycled in accordance with Table 1626 of 2017 Florida Building Code Building.

Maximum Cyclic Load Test Pressure: +120 psf & -120 psf

Specimens 2, 3, 4

Positive Load							
Range of Test	Actua	I				# of Cycles	
+0.2 to +0.5 DP	24.0	psf	to	60.0	psf	3,500	
+0.0 to +0.6 DP	0.00	psf	to	72.0	psf	300	
+0.5 to +0.8 DP	60.0	psf	to	96.0	psf	600	
+0.3 to +1.0 DP	36.0	nsf	to	120.0	nsf	100	

Test Results - TAS 203 (continued)

Test

Cyclic Wind Pressure Loading

Negative Loads

Range of Test	Actual					# of Cycles
-0.3 to -1.0 DP	36.0	psf	to	120.0	psf	50
-0.5 to -0.8 DP	60.0	psf	to	96.0	psf	1,050
-0.0 to -0.6 DP	00.0	psf	to	72.0	psf	50
-0.2 to -0.5 DP	24.0	psf	to	60.0	psf	3,350

NOTE: Specimens showed no resultant failure distress or permanent deformation with a recovery of at least 90% over maximum deflection after cycle test. No failure of fasteners or separation of glass from the frame.

Test Method

Test

ASTM F588

Forced Entry Resistance

Type D Window Assembly/ Grade 10: = Pass

Specimen 1

<u>Test</u>

Disassembly = No Entry Sash Manipulation = No Entry

NOTE: 1. T1 = 5 minutes, L1 = 667 N (150 lbf), L2 = 333 N (75 lbf), L3 = 111 N (25 lbf)

2. Loads were held for 60 seconds.

Test Observers

Justin Bupp NCTL, Inc. Robert DeFayette NCTL, Inc.

Keith Mazzie Acurlite Structural Skylights Kyle Mayleth Acurlite Structural Skylights

Where required, plastic film (2-mil) was used to seal against air leakage. The film did not affect the performance of the specimens or influence the results of the tests. All tests were conducted in accordance with the TAS 201, TAS 202 and TAS 203 test methods. Upon completion of all testing, the specimens meet the requirements of Sections 1606, 1620 and 1626 of the "Florida Building Code, Building" and the TAS 201, 202 and 203 protocols.

This test report was prepared by National Certified Testing Laboratory (NCTL), for the exclusive use of the above named client and it does not constitute certification of this product. The results are for the particular specimen tested and do not imply the quality of similar or identical products manufactured or installed from specifications identical to the tested product. All testing was performed in compliance with the referenced test method or specification and any deviations are noted. Ambient conditions during the referenced testing are available upon request. Any film employed during testing had no effect upon test results.

The test specimen was supplied to NCTL by the above named client. No conclusions of any kind regarding the adequacy or inadequacy of the glass in the test specimen are to be drawn from the ASTM E330-02(10) test. Forced entry resistance test equipment used is in compliance with Section 7 of the ASTM F588-07 test method. NCTL is a testing lab and assumes that all information provided by the client is accurate and does not guarantee or warranty any product tested or installed.

Detailed drawings were available for laboratory records and compared to the test specimen at the time of this report. Component drawings were reviewed for product verification. The bill of materials contains details with any deviations noted. Ambient conditions during the referenced testing are available upon request. A copy of this report along with representative sections of the test specimen will be retained by NCTL. This report does not constitute certification or approval of the product, which may only be granted by a certification program validator or recognized approval entity. All tests were conducted in full compliance with the referenced specifications and/or test methods. This report may not be reproduced, except in full, without the written consent of NCTL.

National Certified Testing Laboratories

DIGITAL SIGNATURE

Justin L. Bupp

Joseph A. Reed, PE

Appendix A

Revision Log

<u>Identification</u>	<u>Date</u>	Page & Revision
Original Issue	08/27/19	Not Applicable
Revision 01	03/31/21	Added PE stamped drawings
Revision 02	01/05/22	Reviewed and sealed by Florida PE

Appendix B

Drawings


Component Drawings, with Applicable Part Numbers, Manufacturing and Modeling Details, were reviewed (as submitted) for Product Verification. Detailed assembly drawings showing wall thicknesses of all members, corner construction and hardware application are on file and have been compared to the test sample submitted.


(Reference: NCTL-110-20884-2)


See Attached Documentation; any deviations noted.


Note: The above referenced component drawings (if applicable) along with representative sections of the test specimen will be retained by NCTL per applicable retention requirements. This testing facility assumes that all information provided by the client is accurate.


accordance with the 2020 (7th Ec +120psf and -120psf. 2. The skylight system may be in: 3. These shop drawings are gene 4. Structural adequacy of the sup the supporting structure is the re 5. Design of the supporting struc skylight system (reactions) to the 6. The skylight system indicated in accordance with TAS 2012/20/216	on these shop drawings tested for small missile impact 13. milar materials shall be protected in accordance with s	ects. Design of from the			
PYRAMID	DOUBLE PITCH WITH GABLE	SINGLE PITCH WITH GABLE		acurlite	Out of the same and the same III
				41/8/6 ©	08/0 GM
DOUBLE PITCH WITH HIP	SEGMENTED BARRELL QUATER VAULT WITH GABLE	SEGMENTED BARRELL HALF VAULT WITH GABLE			
STRAIGHT EAVE LEAN-TO WITH GABLE	POLYCON	POLYGON WITH JACK RAFTERS	DADE COUNTY USE	DANGE SERIES SWALL MISSILE	COVERSHEET























Test Specimen Complies With These Details. Any Deviation Is Noted. Report No. 20884-2 By: JB Test Date: 07/25/19

